

ENGINEERING CERTIFICATE

Our Ref: LTR/11832R-Goomax-000

August 2015

This is to certify that at the request of Xiamen Goomax Energy Technology co.,Ltd, Dome Consulting (Aust) Pty Ltd have reviewed the componentry used in the Tile Roof Mounting, Metal Roof Assembly and the Adjustable Solar Mounting Systems Installation Instruction Version 1.0 — updated July 2015.

The elements which were to be checked include:

Rail	GM-R01/R15/R16
Rail Splice Kit	GM-RS-11
Rail Clamp	GM-BR-01
Inter Clamp (30mm, 35mm, 40mm,45mm, 50mm)	GM-MC
End Clamp (30mm, 35mm, 40mm,45mm, 50mm)	GM-EC
Tile Roof Hook	GM-CTH-01
Tin Roof Hook L Leg	GM-MRH-L
Adjustable Tilt Front Leg	GM-AS-B01
Adjustable Tilt Rear Leg	GM-AS
Adjustable Triangle Frame	GM-FT
Klip-Lok 406	GM-MRH-07
Klip-Lok 700	GM-MRH-06

The check included a review of all regions of Australia wind loading conditions including Cyclonic conditions, in accordance to AS1170.2/Amdt2/2012.12.24.

The design and documentation has determined that all supporting componentry in the above mentioned documentation was found to be acceptable.

Attention Installer:

For Solar panels installed on metal roof by using klamp locks inspections by be required by a local qualified Engineer prior to any installation, to ensure the existing metal roof is under suitable conditions

Assumption:

The existing roofing is firmly/properly fixed to the existing roof battens.

Should you have any further queries please do not hesitate to contact me.

Yours faithfully,

FOR & ON BEHALF OF DOME CONSULTING PTY LTD



Robert Cilia
BE (Civil) RBP RPEQ TBP